



**cmpdi**  
A Mini Ratna Company

सेन्ट्रल माइन प्लानिंग एण्ड डिजाइन इन्स्टीच्यूट लिमिटेड  
(कोल इण्डिया लिमिटेड की अनुकूली कंपनी / भारत सरकार का एक लोकल उपकरण)  
गोन्दवाना प्लेस, कांके रोड, रांची - 834 031, झारखण्ड (भारत)  
**Central Mine Planning & Design Institute Limited**  
(A Subsidiary of Coal India Limited / Govt. of India Public Sector Undertaking)  
Gondwana Place, Kanke Road, Ranchi - 834 031, Jharkhand (INDIA)  
**CORPORATE IDENTITY NUMBER - U14292JH1975GO1001223**  
क्षेत्रीय संस्थान-१, वेस्ट एण्ड, जी.टी. रोड, आसन्सोल-७१३३०४  
Regional Institute-1, West End, G.T. Road, Asansol-713304

An ISO 9001: 2015 & ISO 37001: 2016 Certified Company

Ref. No: CMPDIL/RI-I/E&M/2024/ 356

Date: 05.08.2024

### NOTICE INVITING QUOTATION

Sealed quotations are invited from Enlisted / Reputed / Working contractors for Supplying and laying of the new XLPE 1.1 KV grade, 35 sq. mm & 4-core underground cable from Panel room at garage of the office building to mining computer room of office building at CMPDI, RI-1, Asansol as per **Technical Specification & SCHEDULE OF REQUIREMENT (ANNEXURE-I)** and **TERMS & CONDITIONS** given below:-

- a) Date of Availability of Quotation : 05-Aug-24 (from 10.30 AM to 12.00 Noon)
- b) Last date of Availability of Quotation : 19-Aug-24 upto 12.00 Noon.
- c) Last date & time for submission of offer : 20-Aug-24 upto 03:00 PM.
- d) Due date & time of opening of Offer : 20-Aug-24 at 03.30 PM

#### Note:

1. **IF THE QUOTATION IS NOT OPENED ON THE ABOVE DATE, DUE TO UNFORESEEN CIRCUMSTANCES, THEN IT WILL BE OPENED ON THE NEXT WORKING DATE.**
2. **BIDDER OR THEIR AUTHORIZED REPRESENTATIVES MAY ATTEND THE OPENING OF THE QUOTATION. AUTHORISED REPRESENTATIVE MUST PRODUCE A POWER OF ATTORNEY IN HIS FAVOUR**

Quotation can be obtained from the office of **HOD (E&M)/Systems**, CMPDI, RI-1, Asansol during **10.30 AM to 12.00 Noon** on all working days from **05-Aug-24 to 19-Aug-24** upto **12.00 Noon**, free of cost. Quotation can also be downloaded from CMPDI'S website [www.cmpdi.co.in](http://www.cmpdi.co.in) during the period from **05-Aug-24 to 19-Aug-24**.

#### TERMS & CONDITIONS:

##### **1. MODE & METHOD OF SUBMISSION OF QUOTATION**

Quotation must be submitted in sealed cover super-scribing "Supplying and laying of the new XLPE 1.1 KV grade, 35 sq. mm & 4-core underground cable from Panel room at garage of the office building to mining computer room of office building", "Quotation Number, Date & Time of Opening" and should be dropped in the nominated '**TENDER BOX**' kept in the office of the **HOD (E&M) / SYSTEMS**, CMPDI, RI-1, Asansol. Envelopes Stapled shall not be accepted.

2. Sealed quotation shall be opened on **20-Aug-24** at **03.30 PM** in presence of the bidders or their authorised representatives . Authorized Representative must produce power of attorney in his favour.

The offer shall be accompanied with the copies of :-

- a) Electrical contractor license
- b) GST Registration Certificate
- c) PAN No.
- d) Electrical workman permit

3. Bidders should quote the price on **FOR DESTINATION** basis, for delivery to CONSIGNEE/CONSIGNEES END. The offer should indicate, rate per unit and total price **inclusive of all applicable taxes, duties, installation testing & commissioning charges and incidental charges, if any.**

4. The price should be quoted as per the appended format at **Annexure – I.**

5. No Deviation from the terms and conditions of the NIQ shall be accepted, conditional bid should be outright rejected.

6. **NOTE**

- a. **ALL PAGES OF THE OFFER ALONG WITH THE ENCLOSURES ARE TO BE SUBMITTED DULY SIGNED AND STAMPED.**
- b. **OFFERS ERASED, CUTTING AND OVER WRITTEN WILL BE SUMMARILY REJECTED UNLESS CORRECTION IS AUTHENTICATED WITH THE BIDDER'S SIGNATURE.**

7. Offers received after the submission time of the due date of the tender shall not be accepted.

8. **CONSIGNEE**

The Regional Director, CMPDI, RI-1, Asansol – 713 304.

9. **PAYING AUTHORITY**

HOD (F) or his authorized representative.

10. **PAYMENT TERM**

100% of the billed amount will be paid after satisfactory completion of work. **The payment shall be made by e-payment (RTGS/NEFT). Bidders are advised to submit bank detail along with the pre-receipted bill duplicate submitted to HOD (E&M) / SYSTEMS.**

11. **COMPLETION**

The job should be completed within 30 days from the date of issue of work order.

12. **WARRANTY**

You have to provide 1 (One) Year Warranty w. e. f. date of installation/commissioning. Bidders must indicate the Manufacturer's guarantee for the offered item. Only genuine spares will be accepted.

13. **PENALTY**

A sum not exceeding 0.5% per week of the job value which have not been completed for each week or part of the week during the execution of the work subject to maximum of 10% of work value will be recovered from the bill of the party unless subsequent extension of time of completion of work is granted by the Company in writing.

14. **CMPDI, RI-1 reserves the right to accept or reject partly / fully or split-up any or all offers without assigning any reason thereof. No dispute of any kind can be raised against this right of the buyer in any court of law or elsewhere. No correspondence will be entertained in this regard.**

15. **All disputes are subject to Asansol Court Jurisdiction Only.**

This issue with the approval of competent authority.

*Anup Kumar*  
5/8/24  
+ HOD (E&M)

**Copy To:**

1. RD, RI-1, Asansol
2. HOD(P&A)
3. HOD (Fin.), RI-1, Asansol
4. Office Copy.

| S/N                     | Description  | Qty. | Unit | Unit Cost (Rs.) | Total Cost exclusive GST (Rs.) |
|-------------------------|--|------|------|-----------------|--------------------------------|
| 1                       | Laying and fixing of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of following size on wall surface as required.  |      |      |                 |                                |
| 1.1                     | Upto 35 Sq. mm. (clamped with 1 mm thick saddle)   | 20   | Mtrs |                 |                                |
| 2                       | Laying of one number PVC insulated and PVC sheathed /XLPE power cable of 1.1 KV grade of following size direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required.                |      |      |                 |                                |
| 2.1                     | Upto 35 Sq. mm.  | 50   | Mtrs |                 |                                |
| 3                       | Supplying and making end termination with brass compression gland and aluminium lugs for following size of pvc insulated and PVC sheathed /XLPE aluminium conductor cable of 1.1 KV grade as required.                                       |      |      |                 |                                |
| 3.1                     | 4X35 sq. mm(32mm)  | 8    | Nos  |                 |                                |
| 4                       | Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, etc as required. |      |      |                 |                                |
| 4.1                     | 200A,36KA,FPMCCB   | 1    | Nos  |                 |                                |
| 5                       | Dismantling of old XLPE cable at UNDP lab & main substation  | 1    | Nos  |                 |                                |
| 6                       | Supply of Aluminium,XLPE,1.1KV grade, 4 core,35 sq.mm XLPE armoured cable(Stranded conductor)  | 70   | Mtrs |                 |                                |
| 7                       | Supply of 10 sq. mm, single core copper cable  | 6    | Mtrs |                 |                                |
| Total                   |  |      |      |                 | Rs.                            |
| GST@18%                 |  |      |      |                 | Rs.                            |
| Total(Inclusive of GST) |  |      |      |                 | Rs.                            |